

CONSULTANT:

REVISIONS:		
DATE	DESCRIPTION	BY
12/14/16	Revise Per Fall Creek Regional Waste District	
5/10/17	Revise M.H. Elev. MH-E	

APPROVED BY:



Jonathan P. Nolen 4-01-16

THIS DRAWING AND THE IDEAS, DESIGNS
AND CONCEPTS CONTAINED HEREIN ARE
THE EXCLUSIVE INTELLECTUAL PROPERTY
OF TRIAD ASSOCIATES, INC., AND ARE NOT
TO BE USED OR REPRODUCED, IN WHOLE
OR IN PART, WITHOUT THE WRITTEN
CONSENT OF TRIAD ASSOCIATES, INC.



DESIGNED FOR:
D.B. MANN DEVELOPMENT INC.
5035 EAST 76TH STREET COURT
INDIANAPOLIS, INDIANA 46250

SHEET TITLE:	
SANITARY SEWER PLAN PROFILE	
JOB NUMBER: 201450A	
SCALE: 1" = 50'	CHECKED BY:
PLOT SCALE: 1 = 1	PLOT DATE: 5/10/17
DRAWN BY: DWB	DATE:
DESIGNED BY: Jonathan Moen, P.E.	
DRAWING NAME: 201450A-Sanitary Plan Profile	

SHEET No. **3**

3

1.	ALL UTILITY LOCATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL HAVE ALL UTILITIES FIELD VERIFIED AND MARKED PRIOR TO CONSTRUCTION.	5.	THE CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO BECOME FAMILIAR WITH ALL SITE CONDITIONS.
2.	CONTRACTOR SHALL MAINTAIN A MINIMUM 10'-0" HORIZONTAL AND 18" VERTICAL SEPARATION BETWEEN SEWER AND WATER MAINS.	6.	THE CONTRACTOR SHALL PROVIDE THE REQUIRED MEANS FOR MAINTAINING SAFE TRAFFIC AT ALL TIMES.
3.	ALL PROPOSED TOP OF CASTING ELEVATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL ADJUST FINAL ELEVATIONS AS REQUIRED TO BE FLUSH WITH PAVEMENT.	7.	CONTRACTOR SHALL RESTORE ALL DISTURBED LAWN AREAS, STREETS, WALKS, DRIVES, ETC. AS SHOWN ON DRAWINGS, IN THE SPECIFICATIONS, OR TO AT LEAST PRE-EXISTING CONDITIONS.
4.	ALL SEWER TRENCHES SHALL BE BACKFILLED WITH FULL DEPTH COMPACTED GRANULAR BACKFILL ("B" BORROW) UNDER OR WITHIN 5' OF EDGE OF PAVEMENT.	8.	ALL UTILITY CROSSINGS SHALL BE PROTECTED AND SUPPORTED WITH GRANULAR FILL OR CONCRETE AS REQUIRED, PER THE DITIAL SHEET.

10

TREE
EXISTING FIRE HYDRANT
MAILBOX
SIGN
SPOT SHOT
CONTOUR
FENCE
EXIST. COMBINATION
SEWER w/ MANHOLE

- POWER POLE
- MISCELLANEOUS POSTS
- LIGHT POLE
- INLET
- ASPHALT SURFACE
- CONCRETE SURFACE
- STONE SURFACE
- PROPOSED STORM SEWER


 6" W W EXISTING WATER LINE
 10" EXISTING ROAD DRAIN
 2" GAS GAS GAS LINE
 T T UNDERGROUND TELEPHONE LINE
 FO FO EXISTING FIBER OPTIC LINE
 APPROX. RIGHT-OF-WAY

○	EXISTING COMBINATION MANHOLE
○	EXISTING SANITARY MANHOLE
⊗	EXISTING STORM MANHOLE
○	EXISTING TELEPHONE/FIBER OPTIC MANHOLE
> —————> —	EXISTING SANITARY SEWER
> —————> —	EXISTING STORM SEWER
— — — — —	APPROX. PROPERTY LINE
— · — · — · — · —	PROPOSED UTILITY EASEMENT
· · · · ·	EXISTING UTILITY EASEMENT

○	EXISTING COMBINATION MANHOLE
○	EXISTING SANITARY MANHOLE
⊗	EXISTING STORM MANHOLE
○	EXISTING TELEPHONE/FIBER OPTIC MANHOLE
> —————> —	EXISTING SANITARY SEWER
> —————> —	EXISTING STORM SEWER
— — — — —	APPROX. PROPERTY LINE
— · — · — · — · —	PROPOSED UTILITY EASEMENT
· · · · ·	EXISTING UTILITY EASEMENT