USMH - UPSTREAM MANHOLE ALONG LINE SEGMENT DSMH - DOWNSTREAM MANHOLE ALONG LINE SEGMENT *ACCESS AT SOUTH END BY CLEANOUT ONLY

9

SANITARY SEWER CIPP REHABILITATION SCHEDULE			
SEGMENT (USMH-DSMH)	APPROX. LENGTH (LF)	NOMINAL PIPE DIAMETER (IN.)	APPROX. NUMBER OF ACTIVE SERVICE CONNECTION
122-121A	30	8	0
123-122	184	8	3
124-123	404	10	5
124A-124	141	8	0
124A-132	27	10	0
125-124A	99	10	1
126-125	200	10	2
128-126	192	10	0
129-128	361	10	6
130-129	296	8	5
132-133	286	10	4
133-134	326	10	3
135-132	196	8	1
139-135	235	8	4
140-139	60	8	1
141-140	268	8	6
143-144	212	8	3
144-138	292	10	5
145-144	171	10	2
149-134	202	12	1
152-149	249	12	2
157-156	175	8	5
159-158	73	12	0
160-159	459	8	10
161-159	431	12	4
162-161	309	8	4
163-161	50	10	1
166-163	606	10	8
167-166	415	10	5
173-175	29	8	0
174-173	186	8	4
176-180	177	8	0
177-176	250	8	1
178-177	105	10	0
181-180	201	8	3
181A-181	218	8	0
181B-181A	222	8	2
182-181	204	8	2
183-182	330	8	1
184-183	327	8	2

USMH - UPSTREAM MANHOLE ALONG LINE SEGMENT DSMH - DOWNSTREAM MANHOLE ALONG LINE SEGMENT NOTE: ADDITIONAL CIPP SEGMENTS COMPLETED AS NOTED PER **BID ALTERNATE**



C.I.P.P. REHABILITATION SCHEDULE
SANITARY SEWER REHABILITATION
SEWER REHABILITATION PROJECT PHASE II
TOWN OF PENDLETON, INDIANA

MARCH 2017

NONE