

SANITARY SEWER REHABILITATION SCHEDULE - MANHOLE																
Sheet No.	Manhole (MH) No.	MH Material	General Location	MH Diameter (ft.)	MH Depth (ft.)	Surface Type	Grout Leaks, Patch Defects and Apply Cementitious Sealant to all Joints	Full Cementitious Lining	Epoxy Lining	Mastic Chimney Seal	Replace Frame & Cover	Raise Casting	Remove Steps	Install Marker Post	Notes	
PENDLETON AVENUE																
C-01	MH 6-37	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	6.3	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-01	MH 6-36	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	6.9	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-01	MH 6-35	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	7.7	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-01	MH 6-34	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	9.3	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-02	MH 6-33	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	8.1	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-02	MH 6-32	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	8.2	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-02	MH 6-31	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	8.7	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-02	MH 6-30	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	6.9	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-03	MH 6-29	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	13.9	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-03	MH 6-28	PRECAST CONCRETE	WEST OF PENDLETON AVENUE	4	10.0	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	86.0											
GARDEN DRIVE																
C-03	MH 6-38	PRECAST CONCRETE	WEST END OF GARDEN DRIVE	4	4.8	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-03	MH 6-39	PRECAST CONCRETE	APPROX 227 FT. SOUTH OF GARDEN DRIVE	4	5.8	GRAVEL	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	10.6											
REFORMATORY ROAD																
C-04	MH 6-40	PRECAST CONCRETE	SOUTH SIDE OF REFORMATORY ROAD	4	6.7	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	6.7											
HALLOWELL DRIVE																
C-04	MH 2-42	PRECAST CONCRETE	INTERSECTION OF HALLOWELL DR. AND JOHN ST.	4	5.9	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-04	MH 2-45	PRECAST CONCRETE	HALLOWELL DRIVE WITHIN PAVEMENT	4	2.8	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	8.7											
JOHN STREET																
C-04	MH 2-41	PRECAST CONCRETE	WEST EDGE OF JOHN STREET	4	4.6	GRAVEL	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	4.6											
BROADWAY RD																
C-05	MH 5-45	PRECAST CONCRETE	WEST SIDE OF BROADWAY	4	9.9	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
C-05	MH 5-44	PRECAST CONCRETE	WEST SIDE OF BROADWAY	4	5.8	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	15.7											
FALLS PARK DRIVE																
C-06	MH 2-48	PRECAST CONCRETE	NORTH OF FALLS PARK DRIVE	4	4.9	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-06	MH 2-49	PRECAST CONCRETE	NORTH OF FALLS PARK DRIVE	4	6.0	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
C-06	MH 2-50	PRECAST CONCRETE	NORTH OF FALLS PARK DRIVE	4	5.6	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	16.5											
HAYDEN WAY																
C-06	MH 2-59	PRECAST CONCRETE	NORTH SIDE OF INTERSECTION OF HAYDEN WAY AND WATER ST.	4	3.2	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
C-06	MH 2-62	PRECAST CONCRETE	EAST SIDE OF HAYDEN WAY	4	3.5	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	6.7											
EAST STREET																
C-07	MH 2-47	PRECAST CONCRETE	WEST SIDE OF EAST STREET	4	4.2	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-07	MH 2-46	PRECAST CONCRETE	WEST SIDE OF EAST STREET	4	2.7	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	6.9											
WATER STREET																
C-07	MH 2-57	PRECAST CONCRETE	NORTH SIDE OF WATER STREET	4	5.3	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-07	MH 2-58	PRECAST CONCRETE	NORTH SIDE OF WATER STREET	4	5.3	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-07	MH 2-58A	PRECAST CONCRETE	NORTH SIDE OF WATER STREET	4	5.0	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-08	MH 2-60	PRECAST CONCRETE	NORTH SIDE OF WATER STREET	4	5.2	CONCRETE	YES	NO	NO	YES	NO	NO	NO	NO		
C-08	MH 2-61	PRECAST CONCRETE	NORTH SIDE OF WATER STREET	4	4.9	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-08	MH 2-63	PRECAST CONCRETE	SOUTH SIDE OF WATER STREET	4	4.4	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	30.1											
WEST CENTRAL WAY																
C-08	MH 2-64	PRECAST CONCRETE	INTERSECTION OF WEST CENTRAL WAY AND WATER ST.	4	5.2	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-09	MH 2-65	PRECAST CONCRETE	EAST SIDE OF WEST CENTRAL WAY	4	5.1	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-09	MH 2-66	PRECAST CONCRETE	EAST SIDE OF WEST CENTRAL WAY	4	5.1	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	15.4											
EAST CENTRAL WAY																
C-09	MH 2-67	PRECAST CONCRETE	WEST SIDE OF EAST CENTRAL WAY	4	6.5	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-10	MH 2-68	PRECAST CONCRETE	WEST SIDE OF EAST CENTRAL WAY	4	4.3	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-10	MH 2-69	PRECAST CONCRETE	APPROX 200 FT EAST OF EAST CENTRAL WAY IN EASEMENT	4	2.9	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	13.7											
STATE ROAD 67																
C-10	MH 2-70	PRECAST CONCRETE	WEST SIDE OF STATE ROAD 67	4	5.5	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-10	MH 2-71	PRECAST CONCRETE	APPROX 200 FT WEST OF SR 67, JUST WEST OF HAYDEN WAY	4	2.6	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-11	MH 2-72	PRECAST CONCRETE	WEST SIDE OF STATE ROAD 67	4	6.6	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-11	MH 2-73	PRECAST CONCRETE	EAST SIDE OF STATE ROAD 67	4	3.0	GRASS	YES	NO	NO	YES	NO	NO	NO	NO		
C-11	MH 2-74	PRECAST CONCRETE	EAST SIDE OF STATE ROAD 67	4	7.5	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	25.3											
STATE STREET																
C-12	MH 100	PRECAST CONCRETE	EAST SIDE OF EAST STREET	4	6.4	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
C-12	MH 101	PRECAST CONCRETE	WITHIN EASEMENT APPROX 200 FT NORTH OF STATE STREET	4	5.0	GRASS	NO	NO	NO	YES	NO	NO	NO	NO	TO BE REPLACED	
C-12	MH 102	PRECAST CONCRETE	WITHIN EASEMENT APPROX 200 FT NORTH OF STATE STREET	4	6.0	GRASS	NO	NO	NO	YES	NO	NO	NO	NO	TO BE REPLACED	
C-12	MH 103	PRECAST CONCRETE	WITHIN EASEMENT APPROX 200 FT NORTH OF STATE STREET	4	6.0	GRASS	NO	NO	NO	YES	NO	NO	NO	NO	TO BE REPLACED	
C-12	MH 104	PRECAST CONCRETE	NORTH SIDE OF STATE STREET WEST OF RR	4	8.4	GRAVEL	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	31.8											
EAST STREET																
C-13	MH 105	PRECAST CONCRETE	INTERSECTION OF EAST AND WATER	4	4.2	ASPHALT	YES	NO	NO	YES	NO	NO	NO	NO		
				Total:	4.2											
				Combined:	282.9											

JOSEPH P. TIERNAN
REGISTERED
No. 19300407
STATE OF INDIANA
PROFESSIONAL ENGINEER

GRW PROJECT NO. 4447-14
SRF NO. WW16074803 ---
ALL RIGHTS RESERVED
THIS DOCUMENT IS THE PROPERTY OF
GRW ENGINEERS, INC. AND SHALL NOT
BE REPRODUCED IN WHOLE OR IN PART
WITHOUT WRITTEN PERMISSION
OF GRW ENGINEERS, INC.



engineering | architecture | geospatial
www.grwinc.com

MANHOLE REHABILITATION SCHEDULE
SANITARY SEWER REHABILITATION
FALL CREEK REGIONAL WASTE DISTRICT
PENDLETON, INDIANA

DESIGNED: GWL
DRAWN: JPT
REVIEWED: JPT
APPROVED: JPT

DATE: APRIL 2016
SCALE: NONE
SHEET NO. C-14