

LEGEND:	
	EXISTING STONE DRIVE
	EXISTING ASPHALT DRIVE
	EXISTING CONTOUR
	EXISTING FENCE
	EXISTING TREE/BUSH
	EXISTING DRAINAGE PIPE
	EXISTING MANHOLE
	EXISTING DRAINAGE INLET
	EXISTING POWER POLE
	EXISTING GUY WIRES
	EXISTING LIGHT POLE
	EXISTING MAILBOX
	EXISTING SECTION LINE
	EXISTING PROPERTY LINE
	EXISTING RIGHT-OF-WAY LINE
	EXISTING EASEMENT
	PROPOSED EASEMENT
	EXISTING SHORE LINE
	EXISTING GAS LINE
	EXISTING WATER LINE
	EXISTING UNDERGROUND ELECTRIC LINE
	PROPOSED FORCEMAIN LOCATION
	PROPOSED AIR/VAC RELEASE
	PROPOSED VALVE w/ BOX & RISER
	PROPOSED SERVICE CONNECTION
	PROPOSED VALVE VAULT

UTILITIES:	
INDIANA GAS COMPANY 2001 LOUISE STREET ANDERSON, INDIANA 46016 CONTACT: MR. MIKE JOHNSON TEL: (317) 592-4500	
GTE 1191 RICH ROAD RICHMOND, INDIANA 47374 CONTACT: MS. JOANN ANTHONY TEL: (317) 984-2251	
TCI CABLE 335 EAST 10th STREET ANDERSON, INDIANA 46016 CONTACT: MR. ROCKY BENNETT TEL: (765) 649-5228	
CINERGY / PSI 100 MILL CREEK ROAD NOBLESVILLE, INDIANA 46060 CONTACT: MR. TRACY GRADY TEL: (317) 776-5352	
CENTRAL INDIANA POWER 2243 EAST MAIN STREET GREENFIELD, INDIANA 46140 CONTACT: MR. GARY SARGENT TEL: (317) 462-4417	
INGALLS WATER 249 NORTH MERIDIAN STREET INGALLS, INDIANA 46048 CONTACT: MR. RANDY McVEY TEL: (317) 485-4321	
SPRINT 50 NORTH JACKSON STREET FRANK, INDIANA 46131 CONTACT: MS. NANCY PICKEREL TEL: (317) 736-5309	

TEMPORARY BENCHMARK INFORMATION:	
TBM #1a	BOX NOTCH CUT IN THE NORTHWEST CORNER OF THE SECOND LIGHT POLE CONCRETE PAD. THIS TBM IS ON THE TREATMENT PLANT SITE. ELEV. 842.36
TBM #1	SPIKE IN THE SOUTHEAST SIDE OF POWERPOLE #065277 AT THE NORTHWEST QUADRANT OF COUNTY ROAD 650W AND FALL CREEK DRIVE. ELEV. 861.26
TBM #2	SPIKE IN THE SOUTH SIDE OF POWERPOLE #B-2 98 SPPA 454 40 EAST OF 7144 FALL CREEK DRIVE. ELEV. 859.41
TBM #3	SPIKE IN THE SOUTHWEST SIDE OF POWERPOLE AT THE NORTH SIDE OF THE ROAD AT FALL CREEK DRIVE AND COUNTY ROAD 750W. ELEV. 854.43
TBM #4	SPIKE IN A POLE LOCATED 100 FEET WEST OF THE INTERSECTION OF COUNTY ROAD 900S AND COUNTY ROAD 750W. ELEV. 853.20
TBM #5	RAILROAD SPIKE WHICH WAS FOUND AT THE INTERSECTION OF COUNTY ROAD 800W AND COUNTY ROAD 875S. ELEV. 861.90
TBM #6	SPIKE IN THE WEST SIDE OF POWERPOLE #084-393 AT COUNTY ROAD 800S AND COUNTY ROAD 800W. ELEV. 868.44
TBM #7	SPIKE IN THE NORTH SIDE OF POWERPOLE ON COUNTY ROAD 800S. ELEV. 850.14
TBM #8	NOTCHED SQUARE IN WESTERLY BASE OF A LIGHT POLE ON THE NORTH SIDE OF THE I-69 NORTH BOUND ON RAMP. ELEV. 857.56

GENERAL NOTES:	
1.	CONTRACTOR TO FIELD VERIFY ALL EXISTING UTILITIES, STRUCTURES, ELEVATIONS, ETC. PRIOR TO CONSTRUCTION.
2.	CONTRACTOR TO MAINTAIN EXISTING PLANT OPERATION DURING CONSTRUCTION. ANY INTERFERENCE WITH OPERATION NECESSARY MUST BE APPROVED IN WRITING 48 HRS. IN ADVANCE. TREATMENT CANNOT BE JEOPARDIZED.
3.	ALL DISTURBED AREAS TO BE RESTORED TO ORIGINAL CONDITION IF NOT SPECIFIED OTHERWISE.
4.	ALL TEMPORARY PUMPING, BY-PASS STRUCTURES, ETC. NECESSARY SHALL BE INCLUDED IN THE CONTRACTOR'S BID.
5.	ALL 90° PIPING TURNS SHALL BE DONE WITH TWO (2) D.I.M.J. 45° ELBOWS UNLESS OTHERWISE SPECIFIED.
6.	SEE SHEET 21 FOR RESTRAINED JOINT DETAILS.
7.	CONTRACTOR TO TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EXISTING STRUCTURES DURING CONSTRUCTION.
8.	SEE DETAIL SHEET 21 FOR PIPE BEDDING REQUIREMENTS.
9.	SEE SHEETS 20 AND 21 FOR FURTHER PROPOSED PROJECT SPECIFIC DETAIL INFORMATION.
10.	SEE DETAIL SHEET 19 FOR LIFT STATION DETAILS.
11.	CONTRACTOR TO COORDINATE WITH ALL MECHANICAL AND ELECTRICAL WORK TO BE REQUIRED.
12.	CONTRACTOR SHALL CONTACT ALL UTILITIES FOR LOCATION OF EXISTING SERVICES FOR BOTH THE TREATMENT FACILITY AND FORCEMAIN ROUTE PRIOR TO CONSTRUCTION.
13.	SEE PLAN SHEET 20 FOR PROPOSED SERVICE CONNECTION VAULT INFORMATION.

BOARD OF TRUSTEES:

MORRIS E. McCURDY – PRESIDENT
AGON D. TOLBERT – MEMBER
DOUGLAS S. McGEE – MEMBER
DALLAS D. FOSTER – MEMBER
MARK A. JABLONSKI – MEMBER
DAVID K. PADGETT – MEMBER
JACK W. RHODES – MEMBER
EDWARD L. STERGAR, JR. – MEMBER
GREGORY L. VALENTINE – MEMBER

GENERAL MANAGER:

JOE ROWLETT

NOTE:

ADDITIONAL RIGHT-OF-WAY OR EASEMENTS MAY NEED TO BE ACQUIRED FOR INSTALLATION OF SEWER.



DON'T DIG BLIND
CALL BEFORE YOU DIG
1-800-362-5544
1-800-428-5200

PER INDIANA STATE LAW IS-69-1991, IT IS AGAINST THE LAW TO EXCAVATE WITHOUT NOTIFYING THE UNDERGROUND LOCATION SERVICE TWO (2) WORKING DAYS BEFORE COMMENCING WORK.

NOTE: CONTRACTOR TO VERIFY ALL UTILITY LOCATIONS PRIOR TO THE START OF CONSTRUCTION

SHEET INDEX:

SHEET No.	SHEET DESCRIPTION
1	TITLE SHEET
2	INDEX SHEET
3	PROJECT BASE MAP
4	PLANT CONNECTION PLAN AND PROFILE SHEET
5 – 15	PROPOSED SERVICE CONNECTION PLAN WITH EXISTING PLAN AND PROFILE SHEETS
16 – 18	PROPOSED PLAN AND PROFILE AND SERVICE CONNECTIONS
19	LIFT STATION DETAILS
20 – 21	PROPOSED MISCELLANEOUS DETAILS

CONSULTANT:

REVISIONS:

DATE	DESCRIPTION	BY
12-20-04	MISC. REVISIONS	BKY
5-18-06	RECORD DRAWINGS	CJF

APPROVED BY:




RECORD DRAWING

This drawing has been revised from the original contract drawings to allow minor / major changes made during construction. This drawing is not warranted to be complete and accurate in all respects.

GRW Engineers, Inc.

Date: 5-18-06 By: CJF

THIS DRAWING AND THE IDEAS, DESIGNS AND CONCEPTS CONTAINED HEREIN ARE THE EXCLUSIVE INTELLECTUAL PROPERTY OF TRIAD ASSOCIATES, INC., AND ARE NOT TO BE USED OR REPRODUCED, IN WHOLE OR IN PART, WITHOUT THE WRITTEN CONSENT OF TRIAD ASSOCIATES, INC.



TRIAD ASSOCIATES INC.
5835 LAWTON LOOP EAST DRIVE
INDIANAPOLIS, INDIANA 46216
PHONE: 317-377-5230 FAX: 317-377-5241

DESIGNED FOR:

FALL CREEK REGIONAL WASTE DISTRICT
SANITARY SEWER ADDITIONAL
CONNECTIONS AND SERVICE CONNECTIONS

SHEET TITLE:

SHEET INDEX, GENERAL NOTES
AND DRAWING LEGEND SHEET

JOB NUMBER: 200402E	
SCALE: AS NOTED	CHECKED BY: J.W.F.
PLOT SCALE: 1 = 1	PLOT DATE: 12/20/04
DRAWN BY: DAP	DATE: NOVEMBER 2004
DESIGNED BY: Michael P. Hunter, P.E.	
DRAWING NAME: 200402E-IND	

SHEET No.

2

OF 21