

TYPICAL WALK SECTION
SCALE 1"=10'

CROSS SECTION OF LAGOONS
SCALE 1"=10'

OUTFALL LINE
SCALE 1"=10'

APPROVED

JUN 1 1935
TENNESSEE DEPARTMENT OF PUBLIC HEALTH
DIVISION OF SANITARY ENGINEERING
Director

6075-33

AERATOR DIS. SWITCHES
DETAIL A

NOTES:
1. FENCE TO BE CONSTRUCTED WITH 1 1/2" X 36" HIGH C WELSH
WITH TOP & BOTTOM WIRES TO BE 6 GAUGE AND FILLER
WIRES TO BE 11 GAUGE. TO 5 VERTICALS OF 1/2" IN GAUGE
DOUBLE TWISTED WITH 2 BARS ON A SPACE OF 12"
IN DOUBLE GATE SHALL COMPLY OF ABOVE MENTIONED
FENCE WITH 2" X 4" PRESSURE TREATED LAMBER ON ALL
4 SIDES WITH NECESSARY DIAGONALS, HUBS, LOCKS,
EYES, ALL FENCE POSTS TO BE MIN. 4" DIA. PLYWOOD TREATED
AND UNPAILED ON MAX. 14' CENTERED WITH 2" X 4"
DIAGONAL BRACING AT CORNERS (GATE POST SHALL
BE 6" DIA.)
2. SOIL IN CONTACT WITH WELSH SHALL BE 10' X 10' X 1/4" DIRT OR
EQUAL WITH 2" X 4" LAM. (CONC. FILL)

CITY OF LOBELVILLE TENNESSEE			
RECORD OF PLATS		REVISIONS	
NO.	DATE	BY	REVISION
SEWAGE TREATMENT WORKS		SITE PLAN & OUTFALL LINE	
BY: BARGE WAGGONER AND SUMNER, INC.		CHECKED: []	
DATE: []		SCALE: []	
HABSVILLE		TENNESSEE	

