



CONSTRUCTION NOTES:

1. LAY WATER LINES WITH 2'-6" COVER APPROXIMATELY WHERE SHOWN ON PLANS.
2. ALL WATERLINES SHALL BE PVC SDR 21 WITH DUCTILE IRON FITTINGS.

EROSION CONTROL NOTES:

1. All work shall be done in accordance with the Storm Water Pollution Prevention Plan (SWPPP).
2. No work may proceed until a Notice of Coverage (NOC) has been issued by the State of Tennessee Department of Environment and Conservation.
3. SWPPP must be available at the site for review at all times.
4. At a minimum, the Contractor shall install silt fence on the downhill side of the proposed water line construction area.
5. Contractor shall provide ditch checks as required.
6. Contractor shall furnish and install temporary erosion control blanket/matting on all slopes greater than 2.5:1
7. All areas to remain bare more than 15 days must be temporarily stabilized in accordance with the current Best Management Practices (BMP's).
8. Erosion controls shall be checked and repaired if necessary at least twice each calendar week in accordance with the SWPPP.
9. All erosion control measures utilized within State of Tennessee ROW's shall meet or exceed the TDOT requirements.

Tennessee

River

**CALL BEFORE YOU DIG**

IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT UTILITY COMPANIES PRIOR TO ANY CONSTRUCTION. THE LOCATION OF UTILITIES SHOWN ON THESE PLANS ARE APPROXIMATE AND POSSIBLY INCOMPLETE. THEREFORE CERTIFICATION TO THE LOCATION OF ALL UNDERGROUND UTILITIES IS WITHHELD.

UTILITY COMPANIES TO CALL:

1 - 800 - 351-1111

THREE WORKING DAYS BEFORE YOU DIG

STA. 15+75  
D.C. BOAT DOCK RD. LINE  
INSTALL:  
1 4" x 4" x 4" TEE  
1 - 4" GATE VALVE ASSEMBLY

EXIST. 2" W.L. TO  
BE ABANDON

END  
UNNAMED RD. # 4 LINE  
STA. 7+50  
CONNECT TO NEW 4"x4"x4"  
TEE

END  
D.C. BOAT DOCK RD. LINE  
STA. 26+00  
INSTALL:  
1 - 4" BLOW OFF ASSEMBLY

EXIST. 2" W.L. TO  
BE ABANDON

EXIST. 2" W.L.  
NEW 4" PVC W.L. SDR 21

EXIST. WELL HOUSE,  
2" W.L. & 1 1/2" W.L. TO  
BE ABANDON

BEGIN:  
UNNAMED RD. # 4 LINE  
STA. 0+00  
CONNECT TO NEW 4"x4"x4"  
TEE

BEGIN: DEER CREEK BOAT  
DOCK RD. LINE EXTENSION  
STA. 0+00  
REMOVE EXIST 4" BLOW-OFF  
INSTALL:  
1 - 4" GATE VALVE ASSEMBLY

STA. 5+75  
D.C. BOAT DOCK RD. LINE  
INSTALL:  
1 - 4" GATE VALVE ASSEMBLY  
1 - 4"x4"x4" TEE

INSTALL  
SILT FENCE

STA. 5+00

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL STREAM  
STONE FILTER RING

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

INSTALL  
SILT FENCE

DESIGNED: JWH  
DRAWN: SH  
REVIEWED: JWH  
APPROVED: JWH

DATE: \_\_\_\_\_  
SCALE: AS NOTED  
SHEET NO: C-01

REVISIONS

NO.	DESCRIPTION	DATE	BY

SCALE CHECK: \_\_\_\_\_ THIS MARK SHOULD MEASURE EXACTLY 1" WHEN PLOTTED

DATE: SEPTEMBER 1913

SCALE: AS NOTED

SHEET NO: C-01

CONSTRUCTION DOCUMENTS

GRW PROJECT NO. 3827-02

CLIENT PROJECT NO. \_\_\_\_\_

ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM GRW INC.

engineering | architecture | geospatial

www.grwinc.com

4" PVC DEER CREEK BOAT DOCK RD. LINE EXTENSION

4" PVC UNNAMED RD. #4 LINE

WATER LINE EXTENSION

CITY OF LOBELVILLE AND PERRY COUNTY TENNESSEE