


1. COIR LOGS, GEORIDGE OR SEDIMENT STOP FILTRATION SYSTEM MAY BE USED.
2. INSPECTION OF EROSION CONTROL DEVICES AND STRUCTURES SHALL BE CONDUCTED TWICE EACH WEEK AND AFTER RAIN EVENTS IN EXCESS OF HALF INCH PER DAY. REPAIR OR REPLACEMENT OF DITCH CHECK SHALL BE MADE PROMPTLY AS NEEDED.
3. REMOVE SEDIMENT WHEN SEDIMENT DEPTH AT THE DITCH CHECK IS APPROXIMATELY EQUAL TO ONE-HALF OF COIR LOGS HEIGHT.
4. CHECK DAMS SHALL BE REMOVED UPON COMPLETION OF CONSTRUCTION AND ONLY WHEN DIRECTED BY THE ENGINEER.




TYPE FENCE	A	B	C
TENSILE STRENGTH (LBS. MIN.) (1) (ASTM D-4632)	WARP - 120 FILL - 100	WARP - 120 FILL - 100	WARP - 260 FILL - 180
ELONGATION (% MAX.) (ASTM D-4632)	40	40	40
AOS (APPARENT OPENING SIZE) (MAX. SIEVE SIZE) (ASTM D-4751)	#30	#30	#30
FLOW RATE (GAL./MIN./SQ. FT.) (GDT-87)	25	25	70
ULTRAVIOLET STABILITY (2) (ASTM D-4632 AFTER 300 HOURS WEATHERING IN ACCORDANCE WITH ASTM D-4355)	80	80	80
BURSTING STRENGTH (PSI MIN.) (ASTM D-3786 DIAPHRAGM BURSTING STRENGTH TESTER)	175	175	175
MINIMUM FABRIC WIDTH (INCHES)	36	22	36
(1) MINIMUM ROLL AVERAGE OF FIVE SPECIMENS. (2) PERCENT OF REQUIRED INITIAL MINIMUM TENSILE STRENGTH.			



SILT FENCE DETAIL
SCALE: NTS

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
2. NO WORK MAY PROCEED UNTIL A NOTICE OF COVERAGE (NOC) HAS BEEN ISSUED BY THE STATE OF TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION.
3. SWPPP MUST BE AVAILABLE AT THE SITE FOR REVIEW AT ALL TIMES.
4. AT A MINIMUM, THE CONTRACTOR SHALL INSTALL SILT FENCE ON THE DOWNHILL SIDE OF THE PROPOSED WATER LINE CONSTRUCTION AREA.
5. CONTRACTOR SHALL PROVIDE DITCH CHECKS AS REQUIRED.
6. CONTRACTOR SHALL FURNISH AND INSTALL TEMPORARY EROSION CONTROL BLANKET/MATTING ON ALL SLOPES GREATER THAN 2:5:1
7. ALL AREAS TO REMAIN BARE MORE THAN 15 DAYS MUST BE TEMPORARILY STABILIZED IN ACCORDANCE WITH THE CURRENT BEST MANAGEMENT PRACTICES (BMP'S).
8. EROSION CONTROL SHALL BE CHECKED AND REPAIRED IF NECESSARY AT LEAST TWICE EACH CALENDAR WEEK IN ACCORDANCE WITH THE SWPPP.
9. ALL EROSION CONTROL MEASURES UTILIZED WITHIN STATE OF TENNESSEE ROW'S SHALL MEET OR EXCEED THE TDOT REQUIREMENTS.



NOTE:
FACE OF RIP-RAP IS TO
BE FLUSH WITH SIDES
AND BOTTOM OF DRAIN

RIP-RAP STABILIZATION WHERE NOTED WILL CONSIST OF HAND-PLACED NATIVE LIMESTONE, HAVING A MAXIMUM LENGTH/WIDTH DIMENSION OF 12" IN EITHER DIRECTION AND A MAXIMUM THICKNESS OF 6". TREATMENT WILL BE PLACED IN TWO INTERLOCKING (NESTING) LAYERS. RIP-RAP SHALL BE PLACED FOR THE FULL WIDTH OF AREA DISTURBED BY PIPE LAYING OPERATIONS. LIMIT OF WIDTH FOR PAYMENT OF RIP-RAP SHALL BE AS FOLLOWS:


PIPE DIAMETER	RIP-RAP WIDTH
8"	5'
10"	5.5'
12"	6'
15-16"	8'
18"	8.5'
21"	9'
24"	10'

RIP-RAP DETAIL
SCALE: NTS



SCALE: NTS

SITE PREPARATION (CHANNEL AND SLOPE) – GRADE THE SURFACE INSTALLATION AREAS SO THAT THE GROUND IS SMOOTH AND COMPACT. WHEN SEEDING PRIOR TO INSTALLATION, PREPARE FOR SEEDING BY LOOSENING THE TOP 2" TO 3" OF SOIL. ALL GULLIES, RILLS, AND ANY OTHER DISTURBED AREAS MUST BE FINE GRADED PRIOR TO INSTALLATION. SPREAD SEED BEFORE OR AFTER MAT INSTALLATION AS DIRECTED. (IMPORTANT: REMOVE ALL LARGE ROCKS, DIRT CLOS, STUMPS, ROOTS, GRASS CLUMPS, TRASH, AND OTHER OBSTRUCTIONS FROM THE SOIL SURFACE TO ALLOW FOR INTIMATE CONTACT BETWEEN THE SOIL SURFACE AND THE MAT.)


1. ANCHOR BLANKETS 2' TO 3' OVER THE TOP OF SLOPE AS IN FIG. 1 OR FIG. 2. PIN BLANKETS 1" INTO THE SOIL ALONG THE ANCHOR TRENCH BOTTOM.
2. WALKING BACKWARD DOWN THE SLOPE, LOW ANCHOR BLANKETS MUST BE PLACED IDEALLY THE BLANKET ROLL WILL REST AGAINST YOUR SHIN AS YOU WALK. PLACE BLANKETS CLOSELY TOGETHER TO "LOCK." THE BLANKET MUST BE IN INTIMATE CONTACT WITH THE SOIL TO PERFORM PROPERLY.
3. STAPLE BLANKET ACCORDING TO RECOMMENDED STAPLE PATTERN FOR SPECIFIC PRODUCT AND SLOPE. (SEE STAPLE PATTERN GUIDE.)
4. OVERLAP BLANKETS SIDES (SIDE-TO-SIDE) APPROXIMATELY 3" AND STAPLE ACCORDING TO FIG. 3. NOTE: INSTALL BLANKET SO DOWN SLOPE ARE SHINGLED AWAY FROM PREVAILING WINDS.
5. OVERLAP BLANKET ENDS 6" (15cm), WITH UPSTREAM END OF BLANKET OVERLAPPING STAPLE AT 1" INTERVALS (See FIG. 4 and FIG. 4A) ACROSS WIDTH OF THE BLANKET.
6. CUT EXCESS BLANKET WITH SCISSORS AND ANCHOR AT END OF SLOPE.
7. IF INSTALLED PLANT SPECIES CHECK SLO(TS)™, SEE FIG. 5.



1. EXCAVATE TERMINAL TRENCHES (MINIMUM 12" DEEP AND 6" WIDE) ACROSS THE CHANNEL BOTTOM AT THE UPPER AND LOWER END OF THE LINED CHANNEL SECTIONS. SEE FIG. 1.
2. EXCAVATE LONGITUDINAL TRENCHES (MINIMUM 6" DEEP BY 6" WIDE) ALONG THE CHANNEL EDGES (ABOVE THE WATER LINE) IN WHICH TO BURY THE OUTSIDE BLANKET EDGES. SEE FIG. 2 OR FIG. 3.
3. PLACE THE FIRST BLANKET AT THE DOWNSTREAM (D/S) END OF THE CHANNEL. STAPLE THE CHANNEL TO THE BLANKET AT THE TERMINAL TRENCH AND PIN IT AT 1' INTERVALS ACROSS THE BLANKET WIDTH IN THE BOTTOM OF THE TRENCH.
4. ONCE PINNED AND BACKFILLED, THE BLANKET IS DEPLOYED BY WRAPPING OVER THE TOP OF THE TRENCH AND UNROLLING UPSTREAM (U/S).
5. AT THE CHANNEL IN WIDTH THAN THE PROVIDED ROLLS, PLACE THE ENDS OF THE ADJACENT ROLLS IN THE TERMINAL TRENCH, OVERLAP, AND OVERLAP THE ADJACENT ROLL TO 3" TO 6". PIN THE ROLLS TOGETHER AT THE TRENCH BOTTOM.
6. UNROLL THE BLANKET PROCEEDING U/S AND INTERMEDIATE CHECK SLOTT (MINIMUM 6" DEEP BY 6" WIDE) ACROSS THE WIDTH OF THE CHANNEL 30' INTERVALS. SEE FIG. 4.
7. AT THE CHANNEL END WITHIN THE CHANNEL BOTTOM, EXCAVATE A CHECK SLOTT (MINIMUM 6" DEEP BY 6" WIDE) AND PLACE THE END OF THE D/S BLANKET IN THE BOTTOM OF THE CHECK SLOTT. PLACE THE END OF THE U/S BLANKET OVER THE D/S BLANKET AND STAPLE AT 1' INTERVALS ACROSS THE WIDTH OF THE CHANNEL. PIN THE U/S BLANKET TO THE CHECK SLOTT. ONCE PINNED AND BACKFILLED, THE U/S BLANKET IS DEPLOYED BY WRAPPING OVER THE TOP OF THE TRENCH AND UNROLLING UPSTREAM (U/S). SEE FIG. 5.
8. FOR CHANNEL SLOPES, INTERMITTENT CHECK SLOTS SHOULD BE INSTALLED ACROSS THE WIDTH OF THE CHANNEL AT 30' INTERVALS AND AT THE BEGINNING AND END OF THE CHANNEL. THE TOP EDGE OF THE DOWNSTREAM SIDE BLANKET SHOULD BE PIN ANCHORED IN THE CHANNEL RUMPH RUNNED LONGITUDINALLY IN THE CHANNEL. SEE FIG. 6 OR FIG. 3.
9. ENDS OF ROLLS ON THE SIDE SLOPES SHOULD BE LAPPED 10' AND SHINGLED TO THE WATER FLOW. PIN USING 3 ROWS OF STAPLES, WITH STAPLES SPACED 6" APART. STAPLE THE ROLLS TOGETHER AT 1' INTERVALS ACROSS THE ROLL WIDTH. SEE FIG. 6 AND FIG. 6A.



THIS RECORD DOCUMENT HAS BEEN PREPARED BASED ON INFORMATION PROVIDED BY THE CONSTRUCTION CONTRACTOR. THE ENGINEER HAS REVIEWED TO VERIFY THE ACCURACY AND/OR COMPLETION OF THIS INFORMATION BUT SHALL NOT BE RESPONSIBLE FOR ANY ERRORS OR OMISSIONS WHICH MAY BE INCORPORATED HEREIN AS A RESULT.


GUY Engineers, Inc.
 1000 Highway 100, Suite 100
 Raleigh, NC 27601
 919-876-1100

ENGINEER'S REPRESENTATIVE: Cathy Martin

CONSTRUCTION COMPANY: GRUBBS AND GRUBBS CORP.

DATE: 04/08/2013

EROSION CONTROL BLANKET INSTALLATION GUIDE

This document, originally issued, sealed, and signed by JAMES W. HILBORN, Tennessee Professional Engineer, No. 16514, on 4-08-2013, shall not be used in lieu of a certified document.

GRW PROJECT NO. 3827-03

ALL RIGHTS RESERVED.
THIS DOCUMENT IS THE PROPERTY OF
GROW ENGINEERS, INC. AND SHALL NOT
BE REPRODUCED IN WHOLE OR IN PART
FOR USE FOR CONSTRUCTION OF
ANY OTHER THAN THIS SPECIFIC PROJECT
WITHOUT WRITTEN PERMISSION.

ENGINEERS - ARCHITECTS - PLANNERS
www.grwinc.com

www.grwinc.com

WATER LINE INTERCONNECTION
CITY OF LOBELVILLE, TENNESSEE

[illegible]

DATE:
OCTOBER 2010

SCALE:
AS NOTED

SHEET NO.

C-08