



EROSION CONTROL NOTES:

1. All work shall be done in accordance with the Storm Water Pollution Prevention Plan (SWPPP).
2. No work may proceed until a Notice of Coverage (NOC) has been issued by the State of Tennessee Department of Environment and Conservation.
3. SWPPP must be available at the site for review at all times.
4. At a minimum, the Contractor shall install silt fence on the downhill side of the proposed water line construction area.
5. Contractor shall provide ditch checks as required.
6. Contractor shall furnish and install temporary erosion control blanket/matting on all slopes greater than 2.5:1
7. All areas to remain bare more than 15 days must be temporarily stabilized in accordance with the current Best Management Practices (BMP's).
8. Erosion controls shall be checked and repaired if necessary at least twice each calendar week in accordance with the SWPPP.
9. All erosion control measures utilized within State of Tennessee ROW's shall meet or exceed the TDOT requirements.

FARM GATE TO PRIVATE PROPERTY

INSTALL WATER LINE
1' OFF EDGE OF
PAVEMENT WHERE
POSSIBLE.

MAKE CONNECTION TO
EXISTING 4" WATER LINE
W/PROP. 2" WATER LINE
INSTALL 4"x 2" TAPPING
SLEEVE & VALVE.
BORE & PLACE 250 L.F. 4"
POLYETHYLENE W/ 2" P.E.
CARRIER PIPE CASING

[illegible]