MATCH LINE FOR CONTINUATION – SEE SHEET C-6

MATCH LINE STA. 30+00 FOR CONTINUATION – SEE SHEET C-3

STA. 0+00 = BEGIN LINE
CONNECT TO PROPOSED WATER LINE
INSTALL:
1– 4" X 4" TEE W/ KICKER

STA. 0+00 = BEGIN LINE
CONNECT TO PROPOSED WATER LINE
INSTALL:
1– 6" X 4" TEE W/ KICKER
4" VALVE & BOX

STA. 33+96
CREEK CROSSING
INSTALL:
40 L.F. CONC. ENCASEMENT

CULVERT

STA.41+00
INSTALL:
1– 6" GATE VALVE AND BOX

E1416500
N5155500

STA. 0+00 = BEGIN LINE
CONNECT TO PROPOSED WATER LINE
INSTALL:
1– 6"x 4" TEE & 4"
VALVE & BOX
60 L.F. OF 8" STL. CASING PIPE
(.188 WALL THICKNESS)
TO BE INSTALLED BY BORING & JACKING

PROPOSED 4" PVC WATER LINE

5' OFF E/RD

STA. 15+00 = END OF LINE
INSTALL:
1– 90° BEND W/ KICKER
1– BLOW OFF ASSEMBLY

B.O.

MARION CIRCLE

PROPOSED 4" PVC
WATER LINE

STA. 9+93 = END LINE
CONNECT TO PROPOSED
WATER LINE
INTALL:
1– 6" X 4" TEE
W/ KICKER
4" VALVE & BOX

PROPOSED 6" PVC
WATER LINE

STA. 52+00
INSTALL:
1– 6" GATE VALVE AND BOX

STA. 0+00 = BEGIN LINE
CONNECT TO PROPOSED WATER LINE
INSTALL:
1– 6" X 4" TEE W/ KICKER
4" VALVE & BOX
60 L.F. OF 8" STL. CASING PIPE
(.188 WALL THICKNESS)
TO BE INSTALLED BY BORING & JACKING

DISTRICT LIMITS LINE

PROPOSED 4" PVC WATER LINE

STA. 0+00 = BEGIN LINE
CONNECT TO PROPOSED WATER LINE
INSTALL:
1– 6" X 4" TEE W/ KICKER
4" VALVE & BOX

STA. 6+85 = END OF LINE
INSTALL:
1– 90° BEND W/ KICKER
1– BLOW OFF ASSEMBLY

STA. 9+16 = END OF LINE
CONNECT TO PROPOSED WATER
INSTALL:
1– 4" X 4" TEE W/ KICKER
4" VALVE & BOX

STA. 55+62
INSTALL:
1– 6" GATE
VALVE AND BOX

MATCH LINE STA. 62+00 FOR CONTINUATION – SEE SHEET C-5

5' OFF E/RD

5+00
10+00
15+00
30+00
40+00
45+00
50+00
55+00
60+00

100 0 100

BURIED TELEPHONE CABLES AND UTILITIES
CALL: TENNESSEE ONE CALL (1–800–351–1111)

ALL RIGHTS RESERVED:
THIS DOCUMENT IS THE PROPERTY OF GRW ELROD DUNSON, INC. AND SHALL NOT BE REPRODUCED IN WHOLE OR IN PART OR USED FOR CONSTRUCTION OF OTHER THAN THIS SPECIFIC PROJECT WITHOUT WRITTEN PERMISSION OF GRW ELROD DUNSON INC.

| NO. | DESCRIPTION | DATE | BY |
|---|---|---|---|
| | REVISIONS | | |

JAMES W. HILLSMAN
REGISTERED ENGINEER
No. 16...
STATE OF TENNESSEE

GRW PROJECT NO. 7408-04

PERRY COUNTY
LOBELVILLE, TENNESSEE
WATER LINE EXTENSION, BRITTS LANDING
PROPOSED WATER LINE

GRW Elrod Dunson, Inc.
Engineers, Architects, Planners
LEXINGTON LOUISVILLE INDIANAPOLIS
NASHVILLE KNOXVILLE

| | |
|---|---|
| DESIGNED: JWH | DATE: APRIL, 2002 |
| DRAWN: DLT | SCALE: AS NOTED |
| REVIEWED: KRS | SHEET NO. C-4 |
| APPROVED: JWH | |