PLAN — SURVEYED / PLOTTED / NOTE BOOK / No. / DATE / BY / JOURNAL CHECKED / R/W OR EASE. CHECKED

PROFILE — SURVEYED / PLOTTED / NOTE BOOK / No. / DATE / BY / GRADES CHECKED / R/W OR EASE. CHECKED / STRUCTURE NOTATIONS CHECKED

MH 7-15 STA 17+72

Tank Pump House For Gasoline (Self Bld.)

Match Mark Sta 22+00

Football Field

15" VCP-ES

MH 7-14 STA 45+78

3rd Street

St Albans - Nitro

25' R/W

Pr. Dr.

Tel. Co. M.H.

Edge of Pvmt

Easement

First Avenue

Halstead Flowers

1-Sty Cinder Block

Halstead Office

4' Sidewalk

MH 7-13 STA 40+68

30'

15" VCP-ES

4th Street

AE-13142

AE-13142

AE-R 13137 A 13.2

12" Sewer To Be Abandoned

NOTE:
STA 31+18 TO STA 31+75 PIPE TO BE ENCASED IN CONCRETE SEE DETAIL DWG. NO. 1402.

5th Street

870' Cast Iron Pipe

C&O R/W

C&O R/W Mon.

Connect Overflow To Existing 12" Sewer

Special M.H. See Dwg. 1402

Connect Existing 12" To M.H. 7-7 With 12" Pipe From Existing M.H.

Stone 5' Cor. Mon.

18" C.I.P.

MH 7-7 STA 34+34

MH 7-11 STA 35+34

Concrete Pipes On Approx 18' Centers To Support 14" Cast Iron Pipe See Detail This Sheet

18" VCP-ES

1½-Sty Stucco

Frame Garage

Match Mark Sta 36+00

MH 7-10 STA 38+00

Pontiac Garage

Cab. Pvmt.

Tin Pvmt. Shed

Cinder Blks.

C&O R/W Mon.

6th Street

2-Sty Fr.

1-Sty Fr.

2-Sty Fr.

2-Sty Fr.

2-Sty Fr.

U.S. Route No. 60

Concrete Pier Detail

1.0'

2.0'

Invert Elevations

Sta 31+18

Inv. 580.64

Sta 32+00

Inv. 579.76

Sta 34+50

Inv. 579.83

Sta 36+50

Inv. 578.83

Sta 37+50

Inv. 578.18

Sta 38+00

Inv. 577.68

Sta 38+50

Inv. 577.18

Sta 39+00

Inv. 576.68

Sta 39+50

Inv. 576.18

51' Conc. Encased

Square Conc. Overflow Manhole See Dwg. No. 1402

¢ Profile

141 L.F. of 18" Cast Iron Pipe

143 L.F. of 18" C.I. Pipe On Concrete Piers

V=2%

S=1.7%

D=15"

S=1.1%

D=18"

S=1.7%

D=18"

S=1.7%

D=18"

S=1.7%

D=18"

S=1.7%

600

590

580

570

48 47 46 45 44 43 42 41 40 39 38 37 36 35 34 33

REVISIONS

No.	Date	Description
1	3/1/62	Show Bridge Adjustment
2	7/18/61	Added Conc. Pavg. Brackets & Bends 8" In Dia. Moved Sewer MH 7-6 - MH 7-7
3		
4	9/62	AS BUILT

SANITARY BOARD
CITY OF SAINT ALBANS
KANAWHA COUNTY, WEST VIRGINIA
SEWAGE PROJECT
INTERCEPTOR SEWER
LINE No. 1 STA 22+00 TO STA 38+00

DATE	SCALE HORIZ.	SCALE VERT.	DRWG. NO.
OCTOBER 17, 1961	1" = 50'	1" = 10'	4

W. D. KELLEY, CONSULTING ENGINEER
CHARLESTON, WEST VIRGINIA

PLATE 1 - PLAN-PROFILE

3